



**ADDENDUM #1
November 20, 2018**

**TOWN CENTER PARKING LOT
Bid # ITB-06/18/BS**

TO: ALL PLAN HOLDERS

This Addendum No. 1 to the Contract Documents for City of Winter Springs project "Town Center Parking Lot" is hereby declared a part of the original Contract Documents dated October 2018, and in the case of conflict, the following Addendum No. 1 shall govern. **Bidders shall acknowledge receipt of this Addendum on the Bid Form.**

Project Manual:

1. Section 00300 – Bid Form:

Bid Additive #1 has been removed from the bidding documents. The contractor is to restore all disturbed areas with Bahia sod and water until sod is established, per industry standards. Please replace Bid Form – 2 of 2 (Page 13 of 44) with the updated sheet, attached with this document.

Construction Plans:

2. Construction Plans – Sheet L-1 (Page 5 of 6):

This sheet is no longer apart of the plan set. Please disregard and refer to the Section 00300 change above.

END ADDENDUM

Bid Form

#	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
25	THERMOPLASTIC, BLUE 6"	LF	180		
26	THERMOPLASTIC, HANDICAP SYMBOL	EA	5		
27	THERMOPLASTIC, PREFORMED, ARROWS (STRAIGHT)	EA	8		
28	CONCRETE WHEEL STOPS, BLUE	EA	3		
29	DECORATIVE HANDICAP SIGN AND POLE	EA	5		
30	DECORATIVE STOP SIGN AND POLE	EA	1		
31	2" PVC SLEEVE	LF	254		
32	ELKAY LK4420BF1UDB WATER FOUNTAIN, OR APPROVED EQUAL, INSTALLATION	LS	1		
TOTAL BASE BID (SUM OF ALL ITEMS):					
Pay Item Notes:					
General	The total base bid provided by the contractor shall reflect the total cost for the contractor to complete the project in its entirety. If the contractor determines that the cost for any items of work have not been included in the Bid Form, he/she shall include the cost for those items within another applicable bid item so the proposed Total Base Bid price reflects the total to complete the work in its entirety. If the Bid Additive is not executed, the contractor is responsible for sodding all disturbed areas with Bahia.				
1	The lump sum cost for mobilization cannot exceed 5% of the total base bid. Utility coordination work is to be considered as part of this pay item.				
4	The lump sum price includes the installation of a 6' chain link fence with green opaque fabric prior to any construction activity.				
5	The lump sum item for earthwork includes all cut, fill, import, export, haul off, and disposal of excess or unsuitable soils.				
11	This pay item includes the removal and replacement of sidewalk on the east side of N. Tuskawilla Road. Contractor is to carefully remove any benches, signage, accessories and reinstall them. Pavers in the sidewalk area are not to be reinstalled. The entire stretch of sidewalk is to be concrete.				
12	Pavers are to be Pine Hall ADA Truncated Dome Pavers (Red), or approved equal				
32	The lump sum cost includes a wet tap into an existing 12" ductile iron water main, 3/4" polyethylene tubing, new drain well, and all materials and fittings required for a water meter installation. City is to provide water meter.				